

Summary	Amount						
Subtotal	\$	8,011					
Profit/Overhead	\$	1,602					
Total	S	10.174					

# 1	CSI Ref.	Description				Quantity w/	Uni	it Material	Total	Material	Uni	t Labor			To	tal Item			
		Description	Unit	Quantity	Wastage	Wastage	// Unit Material Cost		Total Material Cost		l Unit Labor Cost		Total Labor Cost			Cost	Tra	rade Cost	
	DIV-01	GENERAL															\$	-	
1																			
1		Permit	LS	1.00	0%	1.00	\$	-	\$	-	\$	-	\$	-	\$	-			
2		Supervision	LS	1.00	0%	1.00	\$	-	\$	-	\$	-	\$	-	\$	-			
3		Final Cleanup	LS	1.00	0%	1.00	\$	-	\$	-	\$	-	\$	-	\$	-			
4		Mobilization Cost	LS	1.00	0%	1.00	\$	-	\$	-	\$	-	\$	-	\$	-			
5		Project Overheads	LS	1.00	0%	1.00	\$	-	\$	-	\$	-	\$	-	\$	-			
6		Bonds	LS	1.00	0%	1.00	\$	-	\$	-	\$	-	\$	-	\$	-			
7		Fees (Architect & Engineer)	LS	1.00	0%	1.00	\$	-	\$	-	\$	-	\$	-	\$	-			
8		Temporary Control & Facilities	LS	1.00	0%	1.00	\$	-	\$	-	\$	-	\$	-	\$	-			
9		Allowance For Lift	LS	1.00	0%	1.00	\$	-	\$	-	\$	-	\$	-	\$	-			
																	_		
	DIV-05	Metals															\$	8,011	
		Wall Framing																	
		wan Frannig				4.5													
		Type 1B - Interior Wall (12'-0"H) (24 LF)																	
10		3-5/8" 20 Gauge Steel Studs @ 16" O.C	LF	216.55	5%	227.38		4.20	\$	955		2.00	\$	455	\$	1,410			
11		3-5/8" Top Tracking	LF	24.00	5%	25.20	\$	4.20	\$	106	\$	2.00	\$	50	\$	156			
12		3-5/8" Bottom Tracking	LF	24.00	5%	25.20	\$	4.20	\$	106	\$	2.00	\$	50	\$	156			
		Type 1A - Interior Wall (12'-0"H) (20 LF)																	
13		3-5/8" 20 Gauge Steel Studs @ 16" O.C	LF	181.00	5%	190.05		4.20		798		2.00		380		1,178			
14		3-5/8" Top Tracking	LF	20.00	5%	21.00		4.20		88		2.00		42		130			
15		3-5/8" Bottom Tracking	LF	20.00	5%	21.00	\$	4.20	\$	88	\$	2.00	\$	42	\$	130			
					U		U												
		Type 2 - Interior Wall (12'-0"H) (57 LF)				STIMATE		4.00		2.26				4.050		2216			
16		3-5/8" 20 Gauge Steel Studs @ 16" O.C	LF	514.00	5%	539.70		4.20		2,267		2.00		1,079		3,346			
17		3-5/8" Top Tracking	LF	57.00	5%	59.85		4.20		251		2.00		120		371			
18		3-5/8" Bottom Tracking	LF	57.00	5%	59.85	\$	4.20	\$	251	\$	2.00	\$	120	\$	371			
		Interior Wall (3'-4"H) (26 LF)																	
19		3-5/8" 20 Gauge Steel Studs @ 16" O.C	SF	65.00	5%	68.25	\$	4.20	S	287	S	2.00	\$	137	\$	423			
20		3-5/8" Top Tracking	LF	26.00	5%	27.30	S	4.20	S	115	S	2.00	S	55	S	169			
21		3-5/8" Bottom Tracking	LF	26.00	5%	27.30		4.20		115		2.00		55		169			
UB TO	OTAI						_	Mat. Cost =	•	5,427	Let	. Cost =	•	2,584	•	8,011			
	ANCE						ľ	5%	•	5,427	Lab	. cost =	3	2,584	\$	401			
	INGEN							2%							\$	160.22			
		AND PROFIT						20%							\$	1,602			
	L BASI							23/0							\$	10,174			

- GENERAL NOTES FOR CONTRACTOR:

 1. Please adjust the Percentage of Insurance, Contingency and OH/Profit as per your requirements.

 2. Please Add the Cost for Items in Div-01 (General) if required.

 3. Please verify the Type and Cost of Equipment with Owner if required.

 4. Online sources are used for prices. Prices may very depending upon field conditions. It is preferable to check prices before bidding.